

## IRIS Touch Firmware Enhancements and Additions From Version 1.9.2 to Version 1.9.3

### Overview

This document details enhancements to the feature set of the IRIS Touch from firmware Version 1.9.2 to Version 1.9.3.

All IRIS Touch diallers can be upgraded by connecting them over IP to our reflash server, so you can be sure of having all the latest facilities, even if you have already taken delivery of the dialler.

### How to Reflash

Connection to the reflash server can be instigated from the installer menu, Settings->Reflash:



The reflash IP address is set by default to Chiron's reflash server (80.176.196.134) and does not need to be changed unless another reflash server is to be used.

The next section of this document is a list of enhancements and additions.

## Enhancements and Additions

### Pin Input Alarms

The maximum number of account code digits allowed when input pins are set to generate SIA format alarms has been increased from 6 to 32 digits.

#### Chiron Security Communications Ltd

Wyvols Court, Swallowfield, Reading  
Berkshire RG7 1WY, United Kingdom  
Telephone: +44 0118 988 0228  
Facsimile: +44 0118 988 1055  
www.chironsc.com  
Email: sales@chironsc.com

Registered office number: 6031811

2nd Floor, Aquis House, 49-51 Blagrove Street  
Reading, Berkshire RG1 1PL United Kingdom

Chiron Security Communications Ltd  
part of the Chi Holding group of companies 

The default SIA messages for input pins 14 and 15 have been changed to make them suitable for use for power supply monitoring, as follows:

	Trouble message	Restore message	Meaning
Input 14	NYP14	NYQ14	Mains power
Input 15	NYT15	NYR15	Battery power